

Lift problems / Cryo refill

- SOP or risk assessment available?
 - If not, write one and consider all cases
- No other access through other building or lifts?
- Dial down air-con




Stair climbers for transport of small pressurised Dewar



- Availability of small pressurised Dewar?
- Availability of stair climber (estates/hire)
- Can be jumpy going up stairs

Electric Pump for Cryogenic Dewar

- Availability of pump and open Dewar?
- Working pressure up to 150mbar/0.5bar
- Carrying of Dewar needed



- In worst case “manual refill” possible and better than a quench but not suggested; still needs transport of nitrogen in larger volumes and takes very long with several magnets